

Appendix 1, Exhibit 3, Plate 2

Tetra Tech, Inc.

TABLE 1 - SCHEDULE OF TEST PITS

New Hope Crushed Stone & Lime Co., Inc. (NHCS)
Solebury Township, Bucks County, PA

TP Designation	Field Collection Date	Latitude	Longitude	Surveyed GS EL (feet)	Inferred Thickness of hardpack (feet)	Inferred Thickness of fill Mat'l (feet)	Depth to Native Ground (ft)	Elevation of Native Ground (ft)
TP-1	6/22/2022	40.37710	-74.97683	116.3	2	5	7	109.3
TP-2	6/22/2022	40.37786	-74.97667	105.2	7	NE	NE	NE
TP-3	6/22/2022	40.37787	-74.97602	100.8	NE	5	5	95.8
TP-4	6/22/2022	40.37891	-74.97624	111.8	2	6	8	103.8
TP-5	6/22/2022	40.37965	-74.97567	110.1	5	NE	5	105.1
TP-6	6/22/2022	40.37753	-74.97668	101.5	NE	9	9	92.5
TP A1	7/12/2023	40.377452	-74.976319	100.9			5.5	95.4
TP A2	7/12/2023	40.377456	-74.975990	100.8			1.5	99.3
TP A3	7/12/2023	40.377566	-74.975981	100.2			7.2	93.0
	7/12/2023	40.377566	-74.975978	97.1			Top of culvert	--
	7/12/2023	40.377566	-74.975976	93.8			Bottom of culvert	--
TP A4	7/12/2023	40.377448	-74.976467	101.1			3.2	97.9
TP A5	7/12/2023	40.378117	-74.976085	103.1			6.7	96.4
TP A6	7/12/2023	40.378098	-74.976372	105.71			8.0	97.7

NE = Not Encountered

GS = Ground Surface

EL = Elevation

Surveyed Ground Surface Elevations provided by Northeast Surveyors on October 3, 2022

Elevations of data collected on July 12, 2023 obtained using an EOS Arrow Gold and Ipad with active cellular service