







Bureau of Mining Programs

2016 Bond Rate Guidelines for the Calculation of Land Reclamation Bonds on Coal Mining Operations

MRAB Meeting April 25, 2016

Bond Rates for 2016 effective April 5

| Unit Operation | Unit Measure | Unit Costs (\$) |
|-------------------------------|--------------|---------------------------------------------------|
| Mobilization/Demobilization | Job | 4% of direct costs or \$40,000, whichever is less |
| Grading (< 500-foot push) | Cubic Yard | 0.90 |
| Grading (≥500-foot push/haul) | Cubic Yard | 1.50 |
| Selective Grading | Acre | 1,700.00 |
| Revegetation | Acre | 1,900.00 |
| Tree Planting | Tree | 0.75 |
| Ditch Excavation | Cubic Yard | 6.25 |
| Jute Matting | Square Yard | 3.80 |
| High Velocity Erosion Control | Square Yard | 3.80 |
| AASHTO No. 1 | Ton | 29.00 |
| AASHTO No. 57 | Ton | 33.00 |
| R3 Rock Lining | Square Yard | 38.00 |
| R4 Rock Lining | Square Yard | 27.00 |
| R5 Rock Lining | Square Yard | 27.00 |
| Geotextile/Filter Fabric | Square Yard | 2.50 |
| PVC Lining ¹ | Square Yard | 12.00 |
| Subsurface Drain | Lineal Foot | 20.00 |
| | | |

Bond Rates for 2016 effective April 5

| Unit Operation | Unit Measure | Unit Costs (\$) |
|-------------------------------------------------------------------------------------------------------------------------|--------------|----------------------------------------|
| Erosion and Sedimentation Control (Temporary Installation) | Job | Lump sum (5% of direct costs for site) |
| Pond Removal Active Phase ² | Pond | 3,800.00 |
| Stage 3 Maintenance Bond Non-Cropland Areas (Land Uses Where Crop Yields Are Not Required) | Acre | 100.00 |
| Stage 3 Maintenance Bond Cropland (Not Row Crops) Pastureland Or Land Occasional Cut For Hay (Excludes Seed Cost) | Acre | 500.00 |
| Stage 3 Maintenance Bond Cropland Area- Row Crops (includes seed cost) | Acre | 800.00 |



Bond Rates for 2016 effective April 5

| Unit Operation | Unit Measure | Unit Costs (\$) |
|-------------------------------------|----------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------|
| Stage 3 Mobilization | Job | 2,500.00 |
| Pond Removal-Stage 3 | Cubic Yards (Embankment Volume) Plus Top Soiling & Revegetation Cost | Use <500 Grading For Pond Embankment Volume Plus Top Soiling & Revegetation Cost For The Area Disturbed |
| Ditch Removal-Stage 3 | Lineal Foot | 0.75 |
| Equipment Tire Removal and Disposal | Tire | 300.00 |

Structure Demolition

Costs Will Be Calculated Using Costs Listed In The Construction Industry's Latest Annual Cost Publications, Such As *Means Building Construction Cost Data*.











Bureau of Mining Programs

Bruce Carl Bureau of Mining Programs 717-787-5103 brcarl@pa.gov