



NOTES:

1. LEVEL SPREADER PIPES TO BE 12-INCH JM EAGLE EAGLE CORR PE PERFORATED PIPE (OR APPROVED EQUAL) AND SHALL BE CAPPED AT BOTH ENDS.
2. LEVEL SPREADER TO BE INSTALLED PARALLEL TO CONTOURS AT LEVEL ELEVATION.
3. PERFORATED PIPE TO BE UNDERLAIN WITH GEOTEXTILE FABRIC AND COVERED WITH AASHTO NO. 1 STONE. MINIMUM STONE COVER SHALL BE 4-INCHES OVER PERFORATED PIPE.
4. ALL LEVEL SPREADER STONE WILL BE REMOVED AND DISTURBED AREA TO BE RESTORED IN ACCORDANCE WITH E&S PLAN.
5. LEVEL SPREADERS TO BE INSTALLED AT ALL TEMPORARY SLOPE PIPE DISCHARGES AT LOW POINTS OF DIVERSION BERM.
6. LEVEL SPREADERS TO BE INSPECTED WEEKLY OR AFTER MEASURABLE RAINFALL EVENT AND SHALL BE MAINTAINED IN GOOD CONDITION AT ALL TIMES.
7. TOTAL REQUIRED LEVEL SPREADER LENGTH TO BE L1 + L2.
8. THE EDGE TO EDGE DIMENSION OF THE MULTIPLE SLOPE PIPES IS CALLED OUT AS A MINIMUM AND MAY BE INCREASED TO FACILITATE INSTALLATION OF SANDBAGS, T-CONNECTIONS, AND ACCESS ACROSS THE SLOPE PIPES.

NO.	DATE	BY	REVISION DESCRIPTION	W.O. NO.	CHK.	APP.

TRANSCONTINENTAL GAS PIPE LINE COMPANY LLC
STANDARD ENVIRONMENTAL DETAIL

CWC

CLEAN WATER CROSSING
(TEMP. MULTIPLE PIPE
LEVEL SPREADER)

