

TEMPORARY LEVEL SPREADER DETAIL NO SCALE

NOTES:

- 1. LEVEL SPREADER PIPES TO BE 12-INCH JM EAGLE EAGLE CORR PE PERFORATED PIPE (OR APPROVED EQUAL) AND SHALL BE CAPPED AT BOTH ENDS.
- 2. LEVEL SPREADER TO BE INSTALLED PARALLEL TO CONTOURS AT LEVEL ELEVATION.
- 3. PERFORATED PIPE TO BE UNDERLAIN AND WRAPPED WITH GEOTEXTILE FABRIC AND COVERED WITH AASHTO NO.

 1 STONE. MINIMUM STONE COVER SHALL BE 4—INCHES OVER PERFORATED PIPE.
- 4. ALL LEVEL SPREADER STONE WILL BE REMOVED AND DISBTURBED AREA TO BE RESTORED IN ACCORDANCE WITH E&S PLAN.
- 5. LEVEL SPREADERS TO BE INSTALLED AT ALL TEMPORARY SLOPE PIPE DISCHARGES AT LOW POINTS OF DIVERSION BERM.
- 6. LEVEL SPREADERS TO BE INSPECTED WEEKLY OR AFTER MEASURABLE RAINFALL EVENT AND SHALL BE MAINTAINED IN GOOD CONDITION AT ALL TIMES.
- 7. TOTAL REQUIRED LEVER SPREADER LENGTH TO BE L1 + L2.