


***HDD PA-BR-0032.0000-RD (S-A47, S-K18, PFO-J47, PEM-J47)***

Given the design, the threat of inadvertent return has been reduced to the maximum extent practicable and in this case that threat is considered to be low. Implementing this design, along with adherence to the Pennsylvania Pipeline Project Inadvertent Return Contingency Plan will ensure inadvertent impacts, if they were to occur, are also minimized to the maximum extent.



The drill will enter/exit 370 feet from the western edge of Wernersville Road and enter/exit 560 feet from the eastern edge. The horizontal directional drill will enter/exit 640 feet from the western edge of N. Sandy Lane and enter/exit 270 feet from the eastern edge. The drill will pass approximately 40 feet below both roads. The geotechnical results, as well as other data points, were used to determine the entry/exit angles, and depths to pass through the best substrates while maintaining the pipe integrity (e.g., no large bends). According to the geotechnical report the primary substrates being drilled through are silty clays and fine sands. Based on the geotechnical report and the drill profile minimal inadvertent returns are expected.



BERKS COUNTY, PENNSYLVANIA - SOUTH HEIDELBERG TOWNSHIP  
S3-0180

PLAN VIEW

PROFILE VIEW



DESIGN AND CONSTRUCTION:

- CONTRACTOR SHALL FIELD VERIFY DEPTH OF ALL EXISTING UTILITIES SHOWN OR NOT SHOWN ON THIS DRAWING.
- THE MINIMUM SEPARATION DISTANCE FROM EXISTING SUBSURFACE UTILITIES SHALL NOT BE LESS THAN 10 FEET AS MEASURED FROM THE OUTSIDE EDGE OF THE UTILITY TO OUTSIDE OF PROPOSED PIPELINE.
- DESIGNED IN ACCORDANCE WITH CFR 49 195 & ASME B31.4
- CROSSING PIPE SPECIFICATION:  
 HDD HORZ. LENGTH (L)=942'  
 HDD PIPE LENGTH (S)=947'  
 20" x 0.456" W.T., X-65, API5L, PSL2, ERW, BFW  
 COATING: 14-16 MILS FBE WITH 30-35 MIL ARO (POWERCRETE R95)
- INTERNAL DESIGN PRESSURE 1480 PSIG (SEAM FACTOR 1.0, DESIGN FACTOR 0.50).
- INSTALLATION METHOD: HORIZONTAL DIRECTIONAL DRILL (HDD).
- PIPELINE WARNING MARKERS SHALL BE INSTALLED ON BOTH SIDES OF ALL ROAD, RAILWAY, AND STREAM CROSSINGS.
- CARRIER PIPE NOT ENCASED.
- PIPE / AMBIENT TEMPERATURE MUST BE NO LESS THAN 30°F DURING PULLBACK WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER.
- CONDUCT 4-HOUR PRE-INSTALLATION HYDROTEST OF HDD PIPE STRING TO MINIMUM 1850 PSIG.
- SEE SUNOCO PENNSYLVANIA PIPELINE PROJECT ESRI WEBMAP FOR ACCESS ROAD ALIGNMENT.
- SUNOCO PIPELINE, L.P.'S HORIZONTAL DIRECTIONAL DRILL INADVERTENT RETURN CONTINGENCY PLAN WILL BE IMPLEMENTED AT ALL TIMES.
- SUNOCO PIPELINE, L.P.'S EROSION AND SEDIMENTATION CONTROL PLAN WILL BE IMPLEMENTED AT ALL TIMES.

**NOTES**

- ALL COORDINATES SHOWN ARE IN LATITUDE AND LONGITUDE. ALL MSL ELEVATIONS ARE NAD83
- STATIONING IS BASED ON HORIZONTAL DISTANCES.
- ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP ARE NOT RESPONSIBLE FOR LOCATION OF FOREIGN UTILITIES SHOWN IN PLOT PLAN OR PROFILE. THE INFORMATION SHOWN HEREON IS FURNISHED WITHOUT LIABILITY ON THE PART OF ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP. FOR ANY DAMAGES RESULTING FROM ERRORS OR OMISSIONS THEREIN.
- CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES. CONTACT ONE CALL AT 811 PRIOR TO DIGGING.
- SUNOCO EMERGENCY HOTLINE NUMBER IS #1-800-786-7440.

| REF. DRAWING |        | REVISIONS   |  |
|--------------|--------|-------------|--|
| ES-5.11      | TO     | ES-5.11     | DESCRIPTION                                  |
| SHEET 6      | TO     | SHEET 6     | AERIAL SITE PLAN                             |
|              |        | EP2         | REVISED PER PADEP COMMENTS RECEIVED 09-06-16 |
|              |        | EP1         | REVISED PER PADEP COMMENTS                   |
|              |        | EP          |  |
|              |        | C           | ADDED GEOTECH INFO                           |
|              |        | B           | ISSUED FOR BID                               |
|              |        | A           | ISSUED FOR REVIEW                            |
| DWG NO       | DWG NO | DESCRIPTION | NO.  |


**Sunoco Logistics Partners L.P.**

**TETRA TECH ROONEY**  
(303) 792-5911

**SUNOCO PIPELINE, L.P.**


20-INCH HORIZONTAL DIRECTIONAL DRILL  
WERNERSVILLE ROAD  
PENNSYLVANIA PIPELINE PROJECT

SCALE: 1"=100'  
DWG. NO: PA-BR-0032.0000-RD



BERKS COUNTY, PENNSYLVANIA - SOUTH HEIDELBERG TOWNSHIP  
S3-0180-16

PROFILE VIEW



NOTE: REFER TO TEST BORING LOG S3-0180 FOR COMPLETE SOIL MATERIAL DESCRIPTION

DESIGN AND CONSTRUCTION:

- CONTRACTOR SHALL FIELD VERIFY DEPTH OF ALL EXISTING UTILITIES SHOWN OR NOT SHOWN ON THIS DRAWING.
- THE MINIMUM SEPARATION DISTANCE FROM EXISTING SUBSURFACE UTILITIES SHALL NOT BE LESS THAN 10 FEET AS MEASURED FROM THE OUTSIDE EDGE OF THE UTILITY TO OUTSIDE OF PROPOSED PIPELINE.
- DESIGNED IN ACCORDANCE WITH CFR 49 195 & ASME B31.4
- CROSSING PIPE SPECIFICATION:  
HDD HORZ. LENGTH (L)=901'  
HDD PIPE LENGTH (S)=907'  
16" x 0.438" W.T., X-70, API5L, PSL2, ERW, BFW  
COATING: 14-16 MILS FBE WITH 30-35 MIL ARO (POWERCRETE R95)
- INTERNAL DESIGN PRESSURE 1480 PSIG (SEAM FACTOR 1.0, DESIGN FACTOR 0.50).
- INSTALLATION METHOD: HORIZONTAL DIRECTIONAL DRILL (HDD).
- PIPELINE WARNING MARKERS SHALL BE INSTALLED ON BOTH SIDES OF ALL ROAD, RAILWAY, AND STREAM CROSSINGS.
- CARRIER PIPE NOT ENCASED.
- PIPE / AMBIENT TEMPERATURE MUST BE NO LESS THAN 30°F DURING PULLBACK WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER.
- CONDUCT 4-HOUR PRE-INSTALLATION HYDROTEST OF HDD PIPE STRING TO MINIMUM 1850 PSIG.
- SEE SUNOCO PENNSYLVANIA PIPELINE PROJECT ESRI WEBMAP FOR ACCESS ROAD ALIGNMENT.
- SUNOCO PIPELINE, L.P.'S HORIZONTAL DIRECTIONAL DRILL INADVERTENT RETURN CONTINGENCY PLAN WILL BE IMPLEMENTED AT ALL TIMES.
- SUNOCO PIPELINE, L.P.'S EROSION AND SEDIMENTATION CONTROL PLAN WILL BE IMPLEMENTED AT ALL TIMES.

NOTES

- ALL COORDINATES SHOWN ARE IN LATITUDE AND LONGITUDE. ALL MSL ELEVATIONS ARE NAD83
- STATIONING IS BASED ON HORIZONTAL DISTANCES.
- ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP ARE NOT RESPONSIBLE FOR LOCATION OF FOREIGN UTILITIES SHOWN IN PLOT PLAN OR PROFILE. THE INFORMATION SHOWN HEREON IS FURNISHED WITHOUT LIABILITY ON THE PART OF ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP. FOR ANY DAMAGES RESULTING FROM ERRORS OR OMISSIONS THEREIN.
- CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES. CONTACT ONE CALL AT 811 PRIOR TO DIGGING.
- SUNOCO EMERGENCY HOTLINE NUMBER IS #1-800-786-7440.

REF. DRAWING

| ES-5.11 | TO | ES-5.11 | DESCRIPTION                                      |
|---------|----|---------|--|
| SHEET 6 | TO | SHEET 6 | AERIAL SITE PLAN                                 |
|         |    |         | EP2 REVISED PER PADEP COMMENTS RECEIVED 09-06-16 |
|         |    |         | EP1 REVISED PER PADEP COMMENTS                   |
|         |    |         | EP   |
|         |    |         | B ADDED GEOTECH INFO                             |
|         |    |         | A ISSUED FOR BID                                 |
| DWG NO  | TO | DWG NO  | DESCRIPTION                                      |

REVISIONS

| BY  | DATE     | CHK | DATE     | APP | DATE     |
|-----|----------|-----|----------|-----|----------|
| MRS | 10/07/16 | RMB | 10/07/16 | AAW | 10/07/16 |
| JTW | 05/09/16 | RMB | 05/09/16 | AAW | 05/09/16 |
| MRS | 02/26/16 | RMB | 02/26/16 | AAW | 02/26/16 |
| MRS | 09/24/15 | RMB | 09/24/15 | AAW | 09/24/15 |
| MRS | 08/31/15 | RMB | 08/31/15 | AAW | 08/31/15 |


**Sunoco Logistics Partners L.P.**

**TETRA TECH ROONEY**  
(303) 792-5911

**SUNOCO PIPELINE, L.P.**

16-INCH HORIZONTAL DIRECTIONAL DRILL  
WERNERSVILLE ROAD  
PENNSYLVANIA PIPELINE PROJECT

SCALE: 1"=100'  
DWG. NO: PA-BR-0032.0000-RD-16



**LEGEND:**

⊙ Geotechnical Soil Boring (SB) Locations



**GEOTECHNICAL BORING LOCATIONS**

HDD S3-0180

BERKS COUNTY, SOUTH HEIDELBERG TOWNSHIP, PA

SUNOCO PENNSYLVANIA PIPELINE PROJECT





**TETRA TECH**

240 Continental Drive, Suite 200  
 Newark, Delaware 19713  
 302.738.7551  
 fax: 302.454.5988

**TEST BORING LOG**

|   |  |                                   |                        |                        |  |
|---|--|-----------------------------------|------------------------|------------------------|--|
| Project Name: SUNOCO PENNSYLVANIA PIPELINE PROJECT        |  |                                   | Project No.: 103IP3406 |                        |  |
| Project Location: WERNERSVILLE ROAD, SOUTH HEIDELBERG TWP |  |                                   | Page 1 of 1            |                        |  |
| HDD No.: S3-0180  |  | Dates(s) Drilled: 12-09-14        |                        | Inspector: E. WATT     |  |
| Boring No.: SB-02   |  | Drilling Method: SPT - ASTM D1586 |                        | Driller: S. HOFFER     |  |
| Drilling Contractor: HAD DRILLING                         |  | Groundwater Depth (ft): 30.0      |                        | Total Depth (ft): 74.3 |  |
| Boring Location Coordinates:                              |  | 40° 18' 29.311" N                 |                        | 76° 3' 22.567" W       |  |

| Sample No. | Sample Depth (ft) |      | Strata Depth (ft) |      | Recov. (in) | Strata (USCS)                         | Description of Materials   | 6" Increment Blows * |    |       |    | N   |  |
|------------|-------------------|------|-------------------|------|-------------|---------------------------------------|--|----------------------|----|-------|----|-----|--|
|            | From              | To   | From              | To   |             |                                       |  |                      |    |       |    |     |  |
|            |                   |      | 0.0               | 0.4  |             |                                       | TOPSOIL (5")   |                      |    |       |    |     |  |
| 1          | 3.0               | 5.0  | 0.4               |      | 18          | INTERLAYERING OF ML, ML/CL, AND CL/ML | MOTTLE BROWN AND ORANGE BROWN SLT AND CLAY WITH SOME FINE SAND, TRACE F-GRAVEL.              | 1                    | 2  | 5     | 6  | 7   |  |
| 2          | 8.0               | 10.0 |                   |      | 18          |                                       | MOTTLED ORANGE TO YELLOW BROWN SILT AND CLAY, AND FINE SAND.                                 | 4                    | 4  | 5     | 5  | 9   |  |
| 3          | 13.0              | 15.0 |                   |      | 22          |                                       | MOTTLED ORANGE BROWN AND LIGHT GRAY CLAY AND SILT, AND FINE SAND. (USCS: CL/ML)              | 1                    | 2  | 6     | 6  | 8   |  |
| 4          | 18.0              | 20.0 |                   |      | 19          |                                       | MOTTLED ORANGE BROWN AND LIGHT GRAY CLAY AND SILT, AND FINE SAND.                            | 2                    | 4  | 5     | 5  | 9   |  |
| 5          | 23.0              | 25.0 |                   |      | 24          |                                       | MOTTLED ORANGE BROWN AND LIGHT GRAY CLAYEY SILT WITH SOME FINE SAND. (USCS: ML)              | 1                    | 1  | 3     | 8  | 4   |  |
| 6          | 28.0              | 30.0 |                   |      | 24          |                                       | MOTTLED LIGHT GRAY AND BROWN SILT/CLAY AND FINE SAND, TRACE UNWEATHERED FINE GRAVEL.         | 1                    | 2  | 3     | 6  | 5   |  |
| 7          | 33.0              | 35.0 |                   |      | 24          |                                       | MOTTLED LIGHT GRAY AND BROWN SILT/CLAY AND FINE SAND, TRACE UNWEATHERED FINE GRAVEL.         | 3                    | 6  | 6     | 8  | 12  |  |
| 8          | 38.0              | 40.0 |                   |      | 20          |                                       | MOTTLED BROWN AND GRAY SILT/CLAY, AND FINE SAND, TRACE UNWEATHERED FINE GRAVEL.              | 1                    | 1  | 4     | 13 | 5   |  |
| 9          | 43.0              | 45.0 |                   |      | 12          |                                       | MOTTLED BROWN AND GRAY CLAY/SILT AND FINE SAND, TRACE UNWEATHERED FINE GRAVEL. (USCS: CL/ML) | 2                    | 5  | 9     | 10 | 14  |  |
| 10         | 48.0              | 50.0 |                   |      | 14          |                                       | MOTTLED BROWN AND GRAY CLAY/SILT AND FINE SAND, TRACE UNWEATHERED FINE GRAVEL.               | WH                   | WH | 1     | 1  | 1   |  |
| 11         | 53.0              | 55.0 |                   |      | 18          |                                       | MOTTLED (SHADES OF BROWN) SILT/CLAY AND FINE SAND, TRACE UNWEATHERED FINE GRAVEL.            | 1                    | 3  | 7     | 15 | 10  |  |
| 12         | 58.0              | 60.0 |                   |      | 17          |                                       | MOTTLED (SHADES OF BROWN) SILT/CLAY AND FINE SAND, TRACE UNWEATHERED FINE GRAVEL.            | 11                   | 26 | 20    | 15 | 46  |  |
| 13         | 63.0              | 65.0 |                   |      | 14          |                                       | MOTTLED (SHADES OF BROWN) SILT/CLAY AND FINE SAND, TRACE UNWEATHERED FINE GRAVEL.            | 4                    | 8  | 10    | 10 | 18  |  |
| 14         | 68.0              | 70.0 |                   |      | 16          |                                       | MOTTLED (SHADES OF BROWN) SILT/CLAY AND FINE SAND, TRACE UNWEATHERED FINE GRAVEL.            | 2                    | 5  | 5     | 6  | 10  |  |
| 15         | 73.0              | 74.3 |                   |      | 12          |                                       | MOTTLED (SHADES OF BROWN) SILT/CLAY AND FINE SAND, TRACE UNWEATHERED FINE GRAVEL.            | 1                    | 17 | 50/4" |    | >50 |  |
|            |                   |      |                   | 74.0 |             |                                       | UNWEATHERED FINE GRAVEL.   |                      |    |       |    |     |  |
|            |                   |      | 74.0              | 74.3 |             |                                       | GRAY LIMESTONE (BROKEN UP)   |                      |    |       |    |     |  |

Notes/Comments:

Pocket Pentrometer Testing

WET ON SPOON AT 33'.  
 CAVED AT 67'  
 WATER LEVEL ON CAVE AT 38'.  
 WATER LEVEL THROUGH AUGERS AT 30'.

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

\* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.  
 N: Number of blows to drive spoon from 6" to 18" interval.



**GEOTECHNICAL LABORATORY TESTING SUMMARY  
SUNOCO PENNSYLVANIA PIPELINE PROJECT  
HDD S3-0180**

| HDD No. | Test Boring No. | Sample No. | Depth of Sample (ft.) |      | Water Content, %<br>(ASTM D2216) | Percent Silts/Clays, %<br>(ASTM D1140) | Atterburg Limits (ASTM D4318) |                  |                     | USCS Classif.<br>(ASTM D2487) |
|---------|-----------------|------------|-----------------------|------|----------------------------------|--|-------------------------------|------------------|---------------------|-------------------------------|
|         |                 |            | From                  | To   |                                  |  | Liquid Limit, %               | Plastic Limit, % | Plasticity Index, % |                               |
| S3-0180 | SB-01           | 2          | 8.0                   | 10.0 | 22.8                             | 70.3                                   | 39                            | 24               | 15                  | CL                            |
|         |                 | 3          | 13.0                  | 15.0 | 32.0                             | 85.4                                   | -                             | -                | -                   | -                             |
|         |                 | 5          | 23.0                  | 25.0 | 25.6                             | 79.5                                   | -                             | -                | -                   | -                             |
|         |                 | 6          | 28.0                  | 30.0 | 28.6                             | 97.4                                   | 37                            | 20               | 17                  | CL                            |
|         | SB-02           | 3          | 13.0                  | 15.0 | 34.3                             | 62.4                                   | 36                            | 24               | 12                  | CL/ML                         |
|         |                 | 5          | 23.0                  | 25.0 | 37.3                             | 79.3                                   | 44                            | 33               | 11                  | ML                            |
|         |                 | 7          | 33.0                  | 35.0 | 28.9                             | 52.5                                   | -                             | -                | -                   | -                             |
|         |                 | 9          | 43.0                  | 45.0 | 35.3                             | 63.2                                   | 39                            | 25               | 14                  | CL/ML                         |
|         |                 | 12         | 58.0                  | 60.0 | 23.8                             | 52.0                                   | -                             | -                | -                   | -                             |
|         | 14              | 68.0       | 70.0                  | 25.6 | 56.9                             | -                                      | -                             | -                | -                   |                               |
|         | SB-03           | 1          | 3.0                   | 5.0  | 23.3                             | 71.7                                   | -                             | -                | -                   | -                             |
|         |                 | 2          | 8.0                   | 10.0 | 44.6                             | 88.0                                   | 34                            | 24               | 10                  | ML/CL                         |
|         |                 | 3          | 13.0                  | 15.0 | 30.5                             | 69.5                                   | 38                            | 24               | 14                  | CL/ML                         |
|         |                 | 5          | 23.0                  | 25.0 | 25.3                             | 52.1                                   | -                             | -                | -                   | -                             |
|         |                 | 6          | 28.0                  | 30.0 | 28.8                             | 59.1                                   | -                             | -                | -                   | -                             |

Notes:

- 1) Sample depths based on feet below grade at time of exploration.



**REGIONAL GEOLOGY SUMMARY  
SUNOCO PENNSYLVANIA PIPELINE PROJECT  
HDD S3-0170**

| HDD No. | NAME              | BORING NO. | REGIONAL GEOLOGY DESCRIPTION  | GENERAL TOPOGRAPHIC SETTING | BEDROCK FORMATION | GENERAL ROCK TYPE     | APPROX MAX FM THICKNESS (FT) | DEPTH TO ROCK (Ft bgs) based on nearby well drilling logs | NOTES / COMMENTS |
|---------|-------------------|------------|---|-----------------------------|-------------------|-----------------------|------------------------------|---|------------------|
| S3-0180 | Vernersville Road | SB-01      | <b>Millbach Fm</b> - Pinkish gray and medium gray laminated limestone and interbeds of light to medium gray finely crystalline dolomite | level upland farmland       | Millbach Fm       | Interbedded limestone | 1,500                        | 40-79   |                  |
|         |                   | SB-02      |   |                             |                   |                       |                              |   |                  |
|         |                   | SB-03      |   |                             |                   |                       |                              |   |                  |

*Note : Source of well log data - <http://www.dcnr.state.pa.us/topogeo/groundwater/pagwis/records/index.htm>. All other sources as referenced in comments section.*

# FIELD DESCRIPTION AND LOGGING SYSTEM FOR SOIL EXPLORATION

## GRANULAR SOILS

(Sand, Gravel & Combinations)

| <u>Density</u> | <u>N (blows)*</u> |
|----------------|-------------------|
| Very Loose     | 5 or less         |
| Loose          | 6 to 10           |
| Medium Dense   | 11 to 30          |
| Dense          | 31 to 50          |
| Very Dense     | 51 or more        |

### Particle Size Identification

|           |   |
|-----------|---|
| Boulders  | 8 in. diameter or more                                  |
| Cobbles   | 3 to 8 in. diameter                                     |
| Gravel    | Coarse (C) 3 in. to ¾ in. sieve                         |
|           | Fine (F) ¾ in. to No. 4 sieve                           |
| Sand      | Coarse (C) No. 4 to No. 10 sieve<br>(4.75mm-2.00mm)     |
|           | Medium (M) No. 10 to No. 40 sieve<br>(2.00mm – 0.425mm) |
|           | Fine (F) No. 40 to No. 200 sieve<br>(0.425 – 0.074mm)   |
| Silt/Clay | Less Than a No. 200 sieve (<0.074mm)                    |

### Relative Proportions

| <u>Description Term</u> | <u>Percent</u> |
|-------------------------|----------------|
| Trace                   | 1 - 10         |
| Little                  | 11 - 20        |
| Some                    | 21 - 35        |
| And                     | 36 - 50        |

## COHESIVE SOILS

(Silt, Clay & Combinations)

| <u>Consistency</u> | <u>N (blows)*</u> |
|--------------------|-------------------|
| Very Soft          | 3 or less         |
| Soft               | 4 to 5            |
| Medium Stiff       | 6 to 10           |
| Stiff              | 11 to 15          |
| Very Stiff         | 16 to 30          |
| Hard               | 31 or more        |

### Plasticity

| <u>Degree of Plasticity</u> | <u>Plasticity Index</u> |
|-----------------------------|-------------------------|
| None to Slight              | 0 - 4                   |
| Slight                      | 5 - 7                   |
| Medium                      | 8 - 22                  |
| High to Very High           | > 22                    |

## ROCK

(Rock Cores)

| <u>Rock Quality Designation (RQD), %</u> | <u>Rock Quality Description</u> |
|--|---------------------------------|
| 0-25                                     | Very Poor                       |
| 25-50                                    | Poor                            |
| 50-75                                    | Fair                            |
| 75-90                                    | Good                            |
| 90-100                                   | Excellent                       |

**\*N - Standard Penetration Resistance.** Driving a 2.0" O.D., 1-3/8" I.D. sampler a distance of 18 inches into undisturbed soil with a 140 pound hammer free falling a distance of 30.0 inches. The number of hammer blows to drive the sampler through each 6 inch interval is recorded; the number of blows required to drive the sampler through the final 12 inch interval is termed the Standard Penetration Resistance (SPR) N-value. For example, blow counts of 6/8/9 (through three 6-inch intervals) results in an SPR N-value of 17 (8+9).

**Groundwater** observations were made at the times indicated. Groundwater elevations fluctuate throughout a given year, depending on actual field porosity and variations in seasonal and annual precipitation.

**UNIFIED SOIL CLASSIFICATION SYSTEM [Casagrande (1948)]**

| Major Divisions   |   | Group Symbols  | Typical Descriptions  | Laboratory Classifications   |   |   |  |  |
|---|---|--|---|--|---|---|--|--|
| Coarse Grained Soils<br>(More than half of material is larger than No. 200 sieve)                       | Gravels<br>(More than half of coarse fraction is larger than No. 4 sieve size)            | Clean gravel<br>(Little or no fines)   | GW<br>Well-graded gravels, gravel-sand mixtures, little or no fines | Determine Percentage of sand and gravel from grain size curve.<br>Depending on Percentage of fines (fraction smaller than No. 200 sieve), coarse-grained soils are classified as follows:<br><br>Less than 5 percent GW, GP, SW, SP<br>More than 12 percent GM, GC, SM, SC<br>5 to 12 percent Borderline cases requiring dual symbols <sup>(1)</sup> | $C_u = \frac{D_{60}}{D_{10}}$ greater than 4: $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ between 1 and 3             |   |  |  |
|   |   | GP<br>Poorly graded gravels, gravel-sand mixtures, little or no fines            | Not meeting $C_u$ or $C_c$ requirements for GW                      |  |   |   |  |  |
|   |   | Gravel with fines<br>(Appreciable amount of fines)                               | GM<br>Silty gravels, gravel-sand-silt mixtures                      |  | Atterberg limits below A Line or $I_p$ less than 4  | Limits plotting in hatched zone with $I_p$ between 4 and 7 are borderline cases requiring use of dual symbols   |  |  |
|   |   |  | GC<br>Clayey gravels, gravel-sand-clay mixtures                     |  |   |   |  |  |
|   | Sands<br>(More than half of coarse fraction is smaller than No. 4 Sieve)                  | Clean sands<br>(Little or no fines)  | SW<br>Well graded sands, gravelly sands, little or no fines         |  | $C_u = \frac{D_{60}}{D_{10}}$ greater than 6: $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ between 1 and 3             |   |  |  |
|   |   |  | SP<br>Poorly graded sands, gravelly sands, little or no fines       |  | Not meeting $C_u$ or $C_c$ requirements for SW  |   |  |  |
|   |   | Sands with fines<br>(Appreciable amount of fines)                                | SM<br>Silty sands, sand-silt mixtures                               |  | Atterberg limits below A Line or $I_p$ less than 4  | Limits Plotting in hatched zone with $I_p$ between 4 and 7 are borderline cases requiring use of dual symbols   |  |  |
|   |   |  | SC<br>Clayey sands, sand-clay mixtures                              |  | Atterberg limits above A line with $I_p$ greater than 7   |   |  |  |
|   |   |  |   |  |   | For soils plotting nearly on A line use dual symbols i.e., $I_p = 29.5$ , $w_L = 60$ gives CH-MH. When $w_L$ is near 50 use CL-CH or ML-MH. Take near as $\pm 2$ percent. |  |  |
|   |   | Fine-grained soils<br>(More than half of material is smaller than No. 200 sieve) | Silt and clays<br>(Liquid limit less than 50)                       |  | ML<br>Inorganic silts and very fine sands, rock flour, silty or clayey fine sands, or clayey silts with slight plasticity |   |  |  |
| CL<br>Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays |   |  |   |  |   |   |  |  |
| OL<br>Organic silts and organic silty clays of low plasticity   |   |  |   |  |   |   |  |  |
| Silt and Clays (Liquid limit greater than 50)   | MH<br>Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts |  |   |  |   |   |  |  |
|   | CH<br>Inorganic clays of high plasticity, fat clays                                       |  |   |  |   |   |  |  |
|   | OH<br>Organic clays of medium to high plasticity, organic silts                           |  |   |  |   |   |  |  |
| Highly organic soils  | Pt<br>Peat and other highly organic soils   |  |   |  |   |   |  |  |

(1) Borderline classifications, used for soils possessing characteristics of two groups, are designated by combinations of group symbols. For example: GW-GC. well-graded gravel-sand mixture with clay binder.