


HDD PA-CH-0413.0000-RD (N Chester Road)

Given the design, the threat of inadvertent return has been reduced to the maximum extent practicable and in this case that threat is considered to be low. Implementing this design, along with adherence to the Pennsylvania Pipeline Project Inadvertent Return Contingency Plan will ensure inadvertent impacts, if they were to occur, are also minimized to the maximum extent.


The drill will enter/exit 400 feet northwest of N Chester Road. The drill will continue under N Chester Road for approximately 3328 feet. This point is 72 feet northwest of the southeast entry/exit point. After the entry/exit point, the drill will pass between 44 and 65 feet under this road. Using the results of the geotechnical investigation, as well as several other data points, the entry/exit, angles, and depths have been configured to pass through the best substrates while maintaining pipe integrity (e.g., no large bends). The majority of the substrate that will be passed through is estimated to be clay, silty sand and gneiss.



PLAN VIEW

CHESTER COUNTY, PENNSYLVANIA - EAST GOSHEN TOWNSHIP
S3-0520

PROFILE VIEW



- DESIGN AND CONSTRUCTION:**
- CONTRACTOR SHALL FIELD VERIFY DEPTH OF ALL EXISTING UTILITIES SHOWN OR NOT SHOWN ON THIS DRAWING.
 - THE MINIMUM SEPARATION DISTANCE FROM EXISTING SUBSURFACE UTILITIES SHALL NOT BE LESS THAN 10 FEET AS MEASURED FROM THE OUTSIDE EDGE OF THE UTILITY TO OUTSIDE OF PROPOSED PIPELINE.
 - DESIGNED IN ACCORDANCE WITH CFR 49 195 & ASME B31.4
 - CROSSING PIPE SPECIFICATION:
HDD HORZ. LENGTH (L-): 3800'
HDD PIPE LENGTH (S-): 3806'
20" x 0.456" W.T., X-65, API5L, PSL2, ERW, BFW
COATING: 14-16 MILS FBE WITH 30-35 MIL ARO (POWERCRETE R95)
 - INTERNAL DESIGN PRESSURE 1480 PSIG (SEAM FACTOR 1.0, DESIGN FACTOR 0.50).
 - INSTALLATION METHOD: HORIZONTAL DIRECTIONAL DRILL (HDD).
 - PIPELINE WARNING MARKERS SHALL BE INSTALLED ON BOTH SIDES OF ALL ROAD, RAILWAY, AND STREAM CROSSINGS.
 - CARRIER PIPE NOT ENCASED
 - PIPE / AMBIENT TEMPERATURE MUST BE NO LESS THAN 30°F DURING PULLBACK WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER
 - CONDUCT 4-HOUR PRE-INSTALLATION HYDROTEST OF HDD PIPE STRING TO MINIMUM 1850 PSIG.
 - SEE SUNOCO PENNSYLVANIA PIPELINE PROJECT ESRI WEBMAP FOR ACCESS ROAD ALIGNMENT.
 - SUNOCO PIPELINE, L.P.'S HORIZONTAL DIRECTIONAL DRILL INADVERTENT RETURN CONTINGENCY PLAN WILL BE IMPLEMENTED AT ALL TIMES.
 - SUNOCO PIPELINE, L.P.'S EROSION AND SEDIMENTATION CONTROL PLAN WILL BE IMPLEMENTED AT ALL TIMES.


NOTES	
1.	ALL COORDINATES SHOWN ARE IN LATITUDE AND LONGITUDE. ALL MSL ELEVATIONS ARE NAD83
2.	STATIONING IS BASED ON HORIZONTAL DISTANCES
3.	ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP ARE NOT RESPONSIBLE FOR LOCATION OF FOREIGN UTILITIES SHOWN IN PLOT PLAN OR PROFILE. THE INFORMATION SHOWN HEREON IS FURNISHED WITHOUT LIABILITY ON THE PART OF ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP. FOR ANY DAMAGES RESULTING FROM ERRORS OR OMISSIONS THEREIN.
4.	CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES. CONTACT ONE CALL AT 811 PRIOR TO DIGGING.
5.	SUNOCO EMERGENCY HOTLINE NUMBER IS #1-800-786-7440.

REF. DRAWING		REVISIONS	
ES-6.68	TO ES-6.68	EROSION & SEDIMENT PLAN	EP1 REVISED PER PADEP COMMENTS
SHEET 43	TO SHEET 45	AERIAL SITE PLAN	EP DESIGN CHANGE
			C ISSUED FOR BID/ADJUSTMENT TO ROW, NO DESIGN CHANGE
			B ISSUED FOR BID
			A ISSUED FOR REVIEW
DWG NO	DWG NO	DESCRIPTION	NO.

BY	DATE	CHK	DATE	APP	DATE
JTW	05/10/16	RMB	05/10/16	AAW	05/10/16
MRS	02/26/16	RMB	02/26/16	AAW	02/26/16
MRS	10/13/15	RMB	10/13/15	AAW	10/13/15
DLM	09/22/15	RMB	09/22/15	AAW	09/22/15
MRS	08/21/15	RMB	08/21/15	AAW	08/21/15
RTT	03/27/15	RMB	03/27/15	AAW	03/27/15




SUNOCO PIPELINE, L.P.	
20-INCH HORIZONTAL DIRECTIONAL DRILL STRASBURG ROAD PENNSYLVANIA PIPELINE PROJECT	
SCALE: 1"=300'	DWG. NO. PA-CH-0413.0000-RD



PLAN VIEW

CHESTER COUNTY, PENNSYLVANIA - EAST GOSHEN TOWNSHIP
S3-0520-16

PROFILE VIEW



- DESIGN AND CONSTRUCTION:
- CONTRACTOR SHALL FIELD VERIFY DEPTH OF ALL EXISTING UTILITIES SHOWN OR NOT SHOWN ON THIS DRAWING.
 - THE MINIMUM SEPARATION DISTANCE FROM EXISTING SUBSURFACE UTILITIES SHALL NOT BE LESS THAN 10 FEET AS MEASURED FROM THE OUTSIDE EDGE OF THE UTILITY TO OUTSIDE OF PROPOSED PIPELINE.
 - DESIGNED IN ACCORDANCE WITH CFR 49 195 & ASME B31.4
 - CROSSING PIPE SPECIFICATION:
HDD HORZ. LENGTH (L-): 3807'
HDD PIPE LENGTH (S-): 3814'
16" x 0.438" W.T., X-70, API5L, PSL2, ERW, BFW
COATING: 14-16 MILS FBE WITH 30-35 MIL ARO (POWERCRETE R95)
 - INTERNAL DESIGN PRESSURE 1480 PSIG (SEAM FACTOR 1.0, DESIGN FACTOR 0.50).
 - INSTALLATION METHOD: HORIZONTAL DIRECTIONAL DRILL (HDD).
 - PIPELINE WARNING MARKERS SHALL BE INSTALLED ON BOTH SIDES OF ALL ROAD, RAILWAY, AND STREAM CROSSINGS.
 - CARRIER PIPE NOT ENCASED
 - PIPE / AMBIENT TEMPERATURE MUST BE NO LESS THAN 30°F DURING PULLBACK WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER
 - CONDUCT 4-HOUR PRE-INSTALLATION HYDROTEST OF HDD PIPE STRING TO MINIMUM 1850 PSIG.
 - SEE SUNOCO PENNSYLVANIA PIPELINE PROJECT ESRI WEBMAP FOR ACCESS ROAD ALIGNMENT.
 - SUNOCO PIPELINE, L.P.'S HORIZONTAL DIRECTIONAL DRILL INADVERTENT RETURN CONTINGENCY PLAN WILL BE IMPLEMENTED AT ALL TIMES.
 - SUNOCO PIPELINE, L.P.'S EROSION AND SEDIMENTATION CONTROL PLAN WILL BE IMPLEMENTED AT ALL TIMES.

NOTES	
1.	ALL COORDINATES SHOWN ARE IN LATITUDE AND LONGITUDE. ALL MSL ELEVATIONS ARE NAD83
2.	STATIONING IS BASED ON HORIZONTAL DISTANCES
3.	ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP ARE NOT RESPONSIBLE FOR LOCATION OF FOREIGN UTILITIES SHOWN IN PLOT PLAN OR PROFILE. THE INFORMATION SHOWN HEREON IS FURNISHED WITHOUT LIABILITY ON THE PART OF ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP. FOR ANY DAMAGES RESULTING FROM ERRORS OR OMISSIONS THEREIN.
4.	CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES. CONTACT ONE CALL AT 811 PRIOR TO DIGGING.
5.	SUNOCO EMERGENCY HOTLINE NUMBER IS #1-800-786-7440.

REF. DRAWING		REVISIONS				
ES-6.68	TO ES-6.68	EROSION & SEDIMENT PLAN				
SHEET 43	TO SHEET 45	AERIAL SITE PLAN	EP1 REVISED PER PADEP COMMENTS			
			EP			
			C DESIGN CHANGE			
			B ISSUED FOR BID/ROW ADJUSTMENT, NO DESIGN CHANGE			
			A ISSUED FOR BID			
DWG NO	DWG NO	DESCRIPTION	NO.	DESCRIPTION	NO.	DESCRIPTION


Sunoco Logistics Partners L.P.

TETRA TECH ROONEY
(303) 792-5911

SUNOCO PIPELINE, L.P.

16-INCH HORIZONTAL DIRECTIONAL DRILL
STRASBURG ROAD
PENNSYLVANIA PIPELINE PROJECT

SCALE: 1"=300' DWG. NO. PA-CH-0413.0000-RD-16



LEGEND:

☉ Geotechnical Soil Boring (SB) Locations



GEOTECHNICAL BORING LOCATIONS
 HDD S3-0520
 CHESTER COUNTY, EAST GOSHEN TWP, PA
 SUNOCO PENNSYLVANIA PIPELINE PROJECT



TETRA TECH

240 Continental Drive, Suite 200
 Newark, Delaware 19713
 302.738.7551
 fax: 302.454.5988

TEST BORING LOG

Project Name: SUNOCO PENNSYLVANIA PIPELINE PROJECT			Project No.: 103IP3406		
Project Location: 544 BEAUMONT CIRCLE, WEST CHESTER, PA			Page 1 of 1		
HDD No.: S3-0510		Dates(s) Drilled: 12-17-15		Inspector: E. WATT	
Boring No.: SB-02		Drilling Method: SPT - ASTM D1586		Driller: S. HOFFER	
Drilling Contractor: HAD DRILLING		Groundwater Depth (ft): SEE BELOW		Total Depth (ft): 30.0	
Boring Location Coordinates:			39°58'26.72"N		75°32'3.30"W

Sample No.	Sample Depth (ft)		Strata Depth (ft)		Recov. (ft)	Strata (USCS)	Description of Materials	6" Increment Blows *				N	
	From	To	From	To									
			0.0	0.3			TOPSOIL (3")						
1	3.0	5.0	0.3		24	CL	BROWN WITH GRAY NODULES, SILTY CLAY, TRACE FINE SAND. (USCS: CL).	1	3	7	9	10	
2	8.0	10.0	6.5		24	SM	REDDISH BROWN FINE SAND AND SILT. (USCS: SM).	4	3	4	5	7	
3	13.0	15.0			5	SM	SAME	3	4	4	6	8	
4	18.0	20.0	16.5		24	SM	DR, VARIEGATED BROWN, WHITE, RED, BLACK FINE TO MEDIUM SAND AND SILT, TRACE FINE ROCK FRAGS.	1	2	3	6	5	
5	23.0	25.0			20	SM	SAME.	4	12	22	23	34	
6	28.0	28.8			8	SM	DR, VARIEGATED BROWN, WHITE, RED, BLACK FINE TO MEDIUM SAND WITH A LITTLE SILT, TRACE FINE ROCK FRAGS.	15	50/4"			>50	
				30.0									
							AUGERED TO 30'.						
							WATER LEVEL THROUGH AUGERS AT 15', MAY BE PERCHED.						
							CAVED AND MOIST AT 22'.						

Notes/Comments:
Pocket Pentrometer Testing DR: DECOMPOSED ROCK
 S1: 2.5 TSF

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
 N: Number of blows to drive spoon from 6" to 18" interval.



TETRA TECH

240 Continental Drive, Suite 200
Newark, Delaware 19713
302.738.7551
fax: 302.454.5988

TEST BORING LOG

Project Name: SUNOCO PENNSYLVANIA PIPELINE PROJECT			Project No.: 103IP3406		
Project Location: N. CHESTER ROAD, WEST CHESTER, PA			Page 1 of 1		
HDD No.: S3-0520		Dates(s) Drilled: 10-29/30-15		Inspector: J. COSTELLO	
Boring No.: SB-01		Drilling Method: SPT - ASTM D1586		Driller: E. ODGEN	
Drilling Contractor: HAD DRILLING		Groundwater Depth (ft): 25.0		Total Depth (ft): 70.0	
Boring Location Coordinates:			39°58'40.81"N		75°32'14.53"W

Sample No.	Sample Depth (ft)		Strata Depth (ft)		Recov. (in)	Strata (USCS)	Description of Materials	6" Increment Blows *				N	
	From	To	From	To									
			0.0	0.5			GRAVEL						
1	3.0	5.0	0.5		23	ML	BROWN SILT WITH A LITTLE FINE SAND, TRACE FINE GRAVEL.	2	2	5	6	7	
				7.0									
2	8.0	10.0	7.0		13	SM	DR, VARIEGATED BROWN, WHITE, RED FINE SAND AND SILT, TRACE FINE GRAVEL (DECOMPOSED SCHIST).	4	2	2	5	4	
3	13.0	15.0			24		SAME	1	1	3	5	4	
4	18.0	20.0			24		DR, GRAY AND WHITE FINE SAND AND SILT, TRACE FINE GRAVEL (DECOMPOSED GNEISS?)	2	2	3	5	5	
5	23.0	25.0			24		SAME	1	2	5	12	7	
6	28.0	30.0			19		SAME	1	1	4	10	5	
7	33.0	35.0			20		DR, GRAYISH BROWN AND WHITE FINE TO MEDIUM SAND AND SILT, TRACE FINE GRAVEL.	1	2	6	11	8	
8	38.0	40.0			19		SAME (USCS: SM)	3	6	18	21	24	
9	43.0	44.3			14		DR, VARIEGATED BLACK, WHITE, BROWN, GRAY FINE TO MEDIUM SAND AND SILT, TRACE FINE GRAVEL.	11	50	50/4"		>50	
10	48.0	50.0			18		DR, VARIEGATED BROWN, WHITE, GRAY, TAND FINE SAND WITH SOME SILT, TRACE FINE GRAVEL.	2	8	13	21	21	
				53.0									
11	53.0	53.8	53.0		7	PARTIALLY WEATHERED GNEISS	BROWN, WHITE, GRAY, AND TAN PARTIALLY WEATHERED GNEISS.	4	50/4"			>50	
12	58.0	58.3			4		SAME	50/4"				>50	
13	63.0	63.4		64.0	2		SAME	50/5"				>50	
							AUGER REFUSAL AT 64'.						
							<u>ROCK CORING</u>						
RUN 1	64.0	67.0	64.0		0		NO RECOVERY	TCR: 0%, SCR: 0%, RQD: 0%					
RUN 2	67.0	70.0		70.0	5		FRAGMENTS OF WHITE AND GRAY GNEISS	TCR: 7%, SCR: 0%, RQD: 0%					

Notes/Comments: Pocket Pentrometer Testing DR: DECOMPOSED ROCK WATER LEVEL THROUGH AUGERS AT 25' CAVED AT 60'.

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
N: Number of blows to drive spoon from 6" to 18" interval.



TETRA TECH

240 Continental Drive, Suite 200
 Newark, Delaware 19713
 302.738.7551
 fax: 302.454.5988

TEST BORING LOG

Project Name: SUNOCO PENNSYLVANIA PIPELINE PROJECT			Project No.: 103IP3406		
Project Location: GLENMONT LANE, WEST CHESTER, PA			Page 1 of 1		
HDD No.: S3-0520		Dates(s) Drilled: 10-28-15		Inspector: J. COSTELLO	
Boring No.: SB-02		Drilling Method: SPT - ASTM D1586		Driller: E. ODGEN	
Drilling Contractor: HAD DRILLING		Groundwater Depth (ft): 29.5		Total Depth (ft): 56.0	
Boring Location Coordinates:			39°58'26.72"N		75°32'3.30"W

Sample No.	Sample Depth (ft)		Strata Depth (ft)		Recov. (ft)	Strata (USCS)	Description of Materials	6" Increment Blows *				N	
	From	To	From	To									
			0.0	0.1			TOPSOIL (<1")						
1	3.0	5.0	0.1		18	ML	ORANGE BROWN CLAYEY SILT WITH A LITTLE FINE SAND, TRACE	1	3	5	5	8	
				9.0			FINE GRAVEL.						
2	8.0	10.0	9.0		24	SM	DR, BROWN TO ORANGE BROWN FINE TO MEDIUM SAND WITH A	1	8	12	4	20	
				12.0			LITTLE SILT, TRACE F-C ROCK FRAGS.						
3	13.0	15.0	12.0		24	MH	DR, ORANGE BROWN SILT AND FINE SAND. (USCS: MH)	1	2	2	3	4	
4	18.0	20.0			24		DR, ORANGE BROWN SILT AND FINE SAND.	1	1	2	4	3	
5	23.0	25.0			24		DR, ORANGE BROWN SILT AND FINE SAND.	1	1	4	7	5	
6	28.0	30.0			24		DR, VARIEGATED GRAY TO YELLOWISH BROWN SILT AND FINE	1	4	8	13	12	
							SAND. (USCS: MH)						
7	33.0	35.0			24		DR, VARIEGATED GRAY TO YELLOWISH BROWN SILT AND FINE	1	4	8	8	12	
				36.5			SAND, SECTION OF FELDSPAR AT 35'.						
8	38.0	40.0	36.5		24		DR, VARIEGATED BROWN AND WHITE FINE SAND AND SILT, WITH	1	3	8	13	11	
						BLACK NODULES.							
9	43.0	44.4			15	SM	DR, VARIEGATED BROWN, BLACK, YELLOW, RED FINE TO COARSE	4	28	50/5"		>50	
							SAND WITH SOME SILT, TRACE FINE ROCK FRAGS.						
10	48.0	49.4			14		SAME	4	28	50/5"		>50	
11	53.0	53.9			8	SAME	11	50/5"			>50		
				56.0									
							AUGER REFUSAL AT 56'.						
							WET ON SPOON AT 29.5'.						
							WATER LEVEL THROUGH AUGERS AT 29.5'.						

Notes/Comments:
Pocket Pentrometer Testing DR: DECOMPOSED ROCK
 S1: 1.5 TSF

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
 N: Number of blows to drive spoon from 6" to 18" interval.



TETRA TECH

240 Continental Drive, Suite 200
 Newark, Delaware 19713
 302.738.7551
 fax: 302.454.5988

TEST BORING LOG

Project Name: SUNOCO PENNSYLVANIA PIPELINE PROJECT			Project No.: 103IP3406		
Project Location: MATLOCK FLORIST, WEST CHESTER, PA			Page 1 of 1		
HDD No.: S3-0520		Dates(s) Drilled: 06-27-15		Inspector: E. WATT	
Boring No.: SB-03		Drilling Method: SPT - ASTM D1586		Driller: S. HOFFER	
Drilling Contractor: HAD DRILLING		Groundwater Depth (ft): 28.0		Total Depth (ft): 30.0	
Boring Location Coordinates:			39° 58' 14.479" N		75° 31' 48.928" W

Sample No.	Sample Depth (ft)		Strata Depth (ft)		Recov. (in)	Strata (USCS)	Description of Materials	6" Increment Blows *				N	
	From	To	From	To									
			0.0	0.3			TOPSOIL (4")						
1	3.0	5.0	0.3		19	ML	LIGHT BROWN AND ORANGE BROWN SILT, TRACE FINE SAND.	1	5	5	9	10	
2	8.0	10.0			22		BROWN, ORANGE BROWN AND LIGHT GRAY MICACEOUS SILT, TRACE FINE SAND.	2	2	4	4	6	
3	13.0	15.0			24		BROWN, ORANGE BROWN, GRAY, AND WHITE SILT, TRACE FINE SAND. (USCS: ML).	2	3	4	4	7	
4	18.0	20.0			24		DR, VARIEGATED BROWN AND ORANGE BROWN MICACEOUS SILT, TRACE FINE SAND.	4	5	11	11	16	
5	23.0	25.0			24		DR, VARIEGATED BROWN, ORANGE BROWN AND WHITE, MICACEOUS SILT, TRACE FINE SAND.	2	4	8	13	12	
6	28.0	30.0			24		DR, VARIEGATED BROWN, ORANGE BROWN AND WHITE, MICACEOUS SILT, TRACE FINE SAND. (USCS: ML).	2	5	9	15	14	
				30.0									
								CAVED AT 29', WATER LEVEL ON CAVE AT 28'.					

Notes/Comments:
Pocket Penetrometer Testing DR: DECOMPOSED ROCK
 10': 1.25 TSF
 15': 1.5 TSF

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
 N: Number of blows to drive spoon from 6" to 18" interval.

**GEOTECHNICAL LABORATORY TESTING SUMMARY
SUNOCO PENNSYLVANIA PIPELINE PROJECT
HDD S3-0520**

HDD No.	Test Boring No.	Sample No.	Depth of Sample (ft.)		Water Content, % (ASTM D2216)	Percent Silts/Clays, % (ASTM D1140)	Atterburg Limits (ASTM D4318)			USCS Classif. (ASTM D2487)
			From	To			Liquid Limit, %	Plastic Limit, %	Plasticity Index, %	
S3-0510	SB-02	1	3.0	5.0	23.3	96.1	43	24	19	CL
		2	8.0	10.0	30.1	47.2	NV	NP	NP	SM
		4	18.0	20.0	35.8	38.9	-	-	-	-
		5	23.0	25.0	24.4	36.6	-	-	-	-
		6	28.0	28.8	9.7	11.2	-	-	-	-
S3-520	SB-01	2	8.0	10.0	29.7	46.2	-	-	-	-
		4	18.0	20.0	25.1	37.2	-	-	-	-
		6	28.0	30.0	25.0	36.7	-	-	-	-
		8	38.0	40.0	22.0	46.4	NV	NP	NP	SM
		10	48.0	50.0	14.9	34.9	-	-	-	-
		12	58.0	58.3	15.4	40.7	NV	NP	NP	SM
	SB-02	1	3.0	5.0	34.7	85.1	-	-	-	-
		2	8.0	10.0	17.6	16.4	-	-	-	-
		3	13.0	15.0	47.1	69.1	65	46	19	MH
		6	28.0	30.0	33.9	60.3	55	37	18	MH
		8	38.0	40.0	28.6	47.0	-	-	-	-
		10	48.0	49.4	11.4	26.4	-	-	-	-
	SB-03	2	8.0	10.0	33.2	93.4	-	-	-	-
		3	13.0	15.0	40.9	98.8	48	35	13	ML
		4	18.0	20.0	35.2	99.0	-	-	-	-
		5	23.0	25.0	25.2	61.3	-	-	-	-
		6	28.0	30.0	35.6	89.3	47	33	14	ML

Rock Core Testing Results				
Boring No.	Core Run	Approximate Depth (ft)	Compressive Strength (psi)	Unit Weight (pcf)
S3-0520, SB-02	1&2	SLIGHT RETRIEVAL IN CORE, MOSTLY DECOMPOSED ROCK SOIL. CORE DID NOT YIELD ROCK THAT COULD BE TESTED FOR COMPRESSIVE STRENGTH		

Notes:

- 1) Sample depths based on feet below grade at time of exploration.

**REGIONAL GEOLOGY SUMMARY
SUNOCO PENNSYLVANIA PIPELINE PROJECT
HDD S3-0520**

HDD No.	NAME	BORING NO.	REGIONAL GEOLOGY DESCRIPTION	GENERAL TOPOGRAPHIC SETTING	BEDROCK FORMATION	GENERAL ROCK TYPE	APPROX MAX FM THICKNESS (FT)	DEPTH TO ROCK (Ft bgs) based on nearby well drilling logs	NOTES / COMMENTS
S3-0510		SB-02	Felsic gneiss - Light, medium grained; includes rocks of probable sedimentary origin.	Generally level, slightly sloping to the south	Felsic gneiss (Precambrian age)	Felsic gneiss; Secondary - paragneiss	No information found during literature review	Bedrock depth information not available within .5 mile radius, likely similar to other formation wells, avg. from approx. 30 to 50 ft bgs	All part of Glenarm Supergroup a name given to provincial series of pre-Cambrian metamorphosed sedimentary rocks present in northern VA, MD, southeastern PA, western NJ, and possibly southeastern NY. Rocks from this assemblage consists of a thick sequence of metasedimentary rock and include the following formations; Setters metaquartzite, Cockeysville marble, Wissahickon Schist (along with subset of the Octoraro schist), Peters Creek metaquartzite and meta siltstones and the Peach Bottom Clate (Geology of Pennsylvania SP-1, 1999) . Drilling in these formations generally difficult to very difficult except where fractures and weathered exposed zones present.
S3-0520		SB-01		Generally level, slightly sloping to the north					
		SB-02		Generally level					
		SB-03		Generally level, slightly sloping to the south					

Note : Source of well log data - <http://www.dcnr.state.pa.us/topogeo/groundwater/pagwis/records/index.htm>. All other sources as referenced in comments section.

FIELD DESCRIPTION AND LOGGING SYSTEM FOR SOIL EXPLORATION

GRANULAR SOILS

(Sand, Gravel & Combinations)

<u>Density</u>	<u>N (blows)*</u>
Very Loose	5 or less
Loose	6 to 10
Medium Dense	11 to 30
Dense	31 to 50
Very Dense	51 or more

Particle Size Identification

Boulders	8 in. diameter or more
Cobbles	3 to 8 in. diameter
Gravel	Coarse (C) 3 in. to ¾ in. sieve Fine (F) ¾ in. to No. 4 sieve
Sand	Coarse (C) No. 4 to No. 10 sieve (4.75mm-2.00mm) Medium (M) No. 10 to No. 40 sieve (2.00mm – 0.425mm) Fine (F) No. 40 to No. 200 sieve (0.425 – 0.074mm)
Silt/Clay	Less Than a No. 200 sieve (<0.074mm)

Relative Proportions

<u>Description Term</u>	<u>Percent</u>
Trace	1 - 10
Little	11 - 20
Some	21 - 35
And	36 - 50

COHESIVE SOILS

(Silt, Clay & Combinations)

<u>Consistency</u>	<u>N (blows)*</u>
Very Soft	3 or less
Soft	4 to 5
Medium Stiff	6 to 10
Stiff	11 to 15
Very Stiff	16 to 30
Hard	31 or more

Plasticity

<u>Degree of Plasticity</u>	<u>Plasticity Index</u>
None to Slight	0 - 4
Slight	5 - 7
Medium	8 - 22
High to Very High	> 22

ROCK

(Rock Cores)

<u>Rock Quality Designation (RQD), %</u>	<u>Rock Quality Description</u>
0-25	Very Poor
25-50	Poor
50-75	Fair
75-90	Good
90-100	Excellent

***N - Standard Penetration Resistance.** Driving a 2.0" O.D., 1-3/8" I.D. sampler a distance of 18 inches into undisturbed soil with a 140 pound hammer free falling a distance of 30.0 inches. The number of hammer blows to drive the sampler through each 6 inch interval is recorded; the number of blows required to drive the sampler through the final 12 inch interval is termed the Standard Penetration Resistance (SPR) N-value. For example, blow counts of 6/8/9 (through three 6-inch intervals) results in an SPR N-value of 17 (8+9).

Groundwater observations were made at the times indicated. Groundwater elevations fluctuate throughout a given year, depending on actual field porosity and variations in seasonal and annual precipitation.

UNIFIED SOIL CLASSIFICATION SYSTEM [Casagrande (1948)]

Major Divisions		Group Symbols	Typical Descriptions	Laboratory Classifications		
Coarse Grained Soils (More than half of material is larger than No. 200 sieve)	Gravels (More than half of coarse fraction is larger than No. 4 sieve size)	Clean gravel (Little or no fines)	GW	Well-graded gravels, gravel-sand mixtures, little or no fines	$C_u = \frac{D_{60}}{D_{10}}$ greater than 4; $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ between 1 and 3 Not meeting C_u or C_c requirements for GW	
			GP	Poorly graded gravels, gravel-sand mixtures, little or no fines		
		Gravel with fines (Appreciable amount of fines)	GM	Silty gravels, gravel-sand-silt mixtures	Atterberg limits below A Line or I_p less than 4	Limits plotting in hatched zone with I_p between 4 and 7 are borderline cases requiring use of dual symbols
			GC	Clayey gravels, gravel-sand-clay mixtures	Atterberg limits above A line with I_p greater than 7	
	Sands (More than half of coarse fraction is smaller than No. 4 Sieve)	Clean sands (Little or no fines)	SW	Well graded sands, gravelly sands, little or no fines	$C_u = \frac{D_{60}}{D_{10}}$ greater than 6; $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ between 1 and 3 Not meeting C_u or C_c requirements for SW	
			SP	Poorly graded sands, gravelly sands, little or no fines		
		Sands with fines (Appreciable amount of fines)	SM	Silty sands, sand-silt mixtures	Atterberg limits below A Line or I_p less than 4	Limits Plotting in hatched zone with I_p between 4 and 7 are borderline cases requiring use of dual symbols
			SC	Clayey sands, sand-clay mixtures	Atterberg limits above A line with I_p greater than 7	
		Determine Percentage of sand and gravel from grain size curve. Depending on Percentage of fines (fraction smaller than No. 200 sieve), coarse-grained soils are classified as follows: Less than 5 percent GW, GP, SW, SP More than 12 percent GM, GC, SM, SC 5 to 12 percent Borderline cases requiring dual symbols ⁽¹⁾				
		Major Divisions		Group Symbols	Typical Descriptions	For soils plotting nearly on A line use dual symbols i.e., $I_p = 29.5$, $w_L = 60$ gives CH-MH. When w_L is near 50 use CL-CH or ML-MH. Take near as ± 2 percent.
Fine-grained soils (More than half of material is smaller than No. 200 sieve)	Silt and clays (Liquid limit less than 50)	ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands, or clayey silts with slight plasticity			
		CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays			
		OL	Organic silts and organic silty clays of low plasticity			
	Silt and Clays (Liquid limit greater than 50)	MH	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts	MH or OH		
		CH	Inorganic clays of high plasticity, fat clays			
		OH	Organic clays of medium to high plasticity, organic silts			
	Highly organic soils	Pt	Peat and other highly organic soils			

(1) Borderline classifications, used for soils possessing characteristics of two groups, are designated by combinations of group symbols. For example: GW-GC. well-graded gravel-sand mixture with clay binder.