HDD PA-YO-0040.0002-RD

Given the design, the threat of inadvertent return has been reduced to the maximum extent practicable and in this case that threat is considered to be low. Implementing this design, along with adherence to the Pennsylvania Pipeline Project Inadvertent Return Contingency Plan will ensure inadvertent impacts, if they were to occur, are also minimized to the maximum extent.

The drill will enter/exit 680 feet from the western edge of Interstate 83 (I-83) and enter/exit 430 feet from the eastern edge. The drill will pass 40 feet below the interstate. The geotechnical results, as well as other data points, were used to determine the entry/exit angles, and depths to pass through the best substrates while maintaining the pipe integrity (e.g., no large bends). According to the geotechnical report primary substrates being drilled through are sandstone and silty clays. Based on the geotechnical report and the drill profile minimal inadvertent returns are expected.



PLAN VIEW

PROFILE VIEW



YORK COUNTY, PENNSYLVANIA - FAIRVIEW TOWNSHIP
S2-0270

GEOTECH SB-01
- NG EL. 748'
- TOPSOIL (0' - 0.8')
- FILL / SC (0.8' - 6.5')
- SILT (USCS:MH) (6.5' - 17.0')
- SANDSTONE (17.0' - 18.1')
- COMPLETION DEPTH EL. 730'

GEOTECH SB-02
- NG EL. 723'
- TOPSOIL (0' - 0.4')
- CL (0.4' - 4.0')
- SC / GC (4.0' - 29.0')
- GROUNDWATER (27.0')
- SANDSTONE (29.0' - 30.2')
- COMPLETION DEPTH EL.693'

GEOTECH SB-03
- NG EL. 725'
- TOPSOIL (0' - 0.5')
- ML (0.5' - 4.8')
- SM (4.8' - 16.5')
- SANDSTONE (16.5' - 17.4')
- COMPLETION DEPTH EL. 708'

NOTE: REFER TO TEST BORING LOG S2-0270 FOR COMPLETE SOIL MATERIAL DESCRIPTION

DESIGN AND CONSTRUCTION:
1. CONTRACTOR SHALL FIELD VERIFY DEPTH OF ALL EXITING UTILITIES SHOWN OR NOT SHOWN ON THIS DRAWING.
2. THE MINIMUM SEPARATION DISTANCE FROM EXISTING SUBSURFACE UTILITIES SHALL NOT BE LESS THAN 10 FEET AS MEASURED FROM THE OUTSIDE EDGE OF THE UTILITY TO OUTSIDE OF PROPOSED PIPELINE.
3. DESIGNED IN ACCORDANCE WITH CFR 49 195 & ASME B31.4
4. CROSSING PIPE SPECIFICATION:
   HDD HORZ. LENGTH (L=): 1200'
   HDD PIPE LENGTH (S=): 1220'
   20" x 0.456" W.T., X-65, API5L, PSL2, ERW, BFW
   COATING: 14-16 MILS FBE WITH 30-35 MIL ARO (POWERCRETE R95)
5. INTERNAL DESIGN PRESSURE 1480 PSIG (SEAM FACTOR 1.0, DESIGH FACTOR 0.50).
6. INSTALLATION METHOD: HORIZONTAL DIRECTIONAL DRILL (HDD).
7. PIPELINE WARNING MARKERS SHALL BE INSTALLED ON BOTH SIDES OF ALL ROAD, RAILWAY, AND STREAM CROSSINGS.
8. CARRIER PIPE NOT ENCASED.
9. PIPE / AMBIENT TEMPERATURE MUST BE NO LESS THAN 30°F DURING PULLBACK WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER.
10. CONDUCT 4-HOUR PRE-INSTALLATION HYDROTEST OF HDD PIPE STRING TO MINIMUM 1850 PSIG.
11. SEE SUNOCO PENNSYLVANIA PIPELINE PROJECT ESRI WEBMAP FOR ACCESS ROAD ALIGNMENT.
12. SUNOCO PIPELINE, L.P.'S HORIZONTAL DIRECTIONAL DRILL INADVERTENT RETURN CONTINGENCY PLAN WILL BE IMPLEMENTED AT ALL TIMES.
13. SUNOCO PIPELINE, L.P.'S EROSION AND SEDIMENTATION CONTROL PLAN WILL BE IMPLEMENTED AT ALL TIMES.

NOTES
1. ALL COORDINATES SHOWN ARE IN LATITUDE AND LONGITUDE. ALL MSL ELEVATIONS ARE NAD83
2. STATIONING IS BASED ON HORIZONTAL DISTANCES.
3. ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP ARE NOT RESPONSIBLE FOR LOCATION OF FOREIGN UTILITIES SHOWN IN PLOT PLAN OR PROFILE. THE INFORMATION SHOWN HEREON IS FURNISHED WITHOUT LIABILITY ON THE PART OF ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP, FOR ANY DAMAGES RESULTING FROM ERRORS OR OMISSIONS THEREIN.
4. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES. CONTACT ONE CALL AT 811 PRIOR TO DIGGING.
5. SUNOCO EMERGENCY HOTLINE NUMBER IS #1-800-786-7440.

REF. DRAWING

DWG NO		DWG NO	DESCRIPTION
ES-4.04	TO	ES-4.11	EROSION & SEDIMENT PLAN
SHEET 7	TO	SHEET 7	AERIAL SITE PLAN

REVISIONS

NO.	DESCRIPTION	BY	DATE	CHK	DATE	APP	DATE
EP2	REVISED PER PADEP COMMENTS RECEIVED 09-06-16	MRS	09/30/16	RMB	09/30/16	AAW	09/30/16
EP1	REVISED PER PADEP COMMENTS	MRS	05/09/16	RMB	05/09/16	AAW	05/09/16
EP		JTW	03/15/16	RMB	03/15/16	AAW	03/15/16
C	ADDED GEOTECH INFO	MRS	09/17/15	RMB	09/17/15	AAW	09/17/15
B	ISSUED FOR BID	MRS	07/31/15	RMB	07/31/15	AWW	07/31/15
A	ISSUED FOR REVIEW	JAM	03/24/15	RMB	03/24/15	AAW	03/24/15

Sunoco Logistics Partners L.P.

TETRA TECH ROONEY (303) 792-5911

SUNOCO PIPELINE, L.P.

20-INCH HORIZONTAL DIRECTIONAL DRILL
I-83
PENNSYLVANIA PIPELINE PROJECT

SCALE: 1"=150' | DWG. NO: PA-YO-0040.0002-RD



PLAN VIEW

PROFILE VIEW



GEOTECH SB-01
- NG EL. 748'
- -TOPSOIL (0' - 0.8')
- -FILL / SC (0.8' - 6.5')
- -SILT (USCS:MH) (6.5' - 17.0')
- -SANDSTONE (17.0' - 18.1')
- -COMPLETION DEPTH EL. 730'

GEOTECH SB-02
- NG EL. 723'
- -TOPSOIL (0' - 0.4')
- -CL (0.4' - 4.0')
- -SC / GC (4.0' - 29.0')
- -GROUNDWATER (27.0')
- -SANDSTONE (29.0' - 30.2')
- -COMPLETION DEPTH EL.693'

GEOTECH SB-03
- NG EL. 725'
- -TOPSOIL (0' - 0.5')
- -ML (0.5' - 4.8')
- -SM (4.8' - 16.5')
- -SANDSTONE (16.5' - 17.4')
- -COMPLETION DEPTH EL. 708'

NOTE: REFER TO TEST BORING LOG S2-0270 FOR COMPLETE SOIL MATERIAL DESCRIPTION

YORK COUNTY, PENNSYLVANIA - FAIRVIEW TOWNSHIP
S2-0270-16

DESIGN AND CONSTRUCTION:
1. CONTRACTOR SHALL FIELD VERIFY DEPTH OF ALL EXITING UTILITIES SHOWN OR NOT SHOWN ON THIS DRAWING.
2. THE MINIMUM SEPARATION DISTANCE FROM EXISTING SUBSURFACE UTILITIES SHALL NOT BE LESS THAN 10 FEET AS MEASURED FROM THE OUTSIDE EDGE OF THE UTILITY TO OUTSIDE OF PROPOSED PIPELINE.
3. DESIGNED IN ACCORDANCE WITH CFR 49 195 & ASME B31.4
4. CROSSING PIPE SPECIFICATION:
   HDD HORZ. LENGTH (L=): 1200'
   HDD PIPE LENGTH (S=): 1220'
   16" x 0.438" W.T., X-70, API5L, PSL2, ERW, BFW
   COATING: 14-16 MILS FBE WITH 30-35 MIL ARO (POWERCRETE R95)
5. INTERNAL DESIGN PRESSURE 1480 PSIG (SEAM FACTOR 1.0, DESIGH FACTOR 0.50).
6. INSTALLATION METHOD: HORIZONTAL DIRECTIONAL DRILL (HDD).
7. PIPELINE WARNING MARKERS SHALL BE INSTALLED ON BOTH SIDES OF ALL ROAD, RAILWAY, AND STREAM CROSSINGS.
8. CARRIER PIPE NOT ENCASED.
9. PIPE / AMBIENT TEMPERATURE MUST BE NO LESS THAN 30°F DURING PULLBACK WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER.
10. CONDUCT 4-HOUR PRE-INSTALLATION HYDROTEST OF HDD PIPE STRING TO MINIMUM 1850 PSIG.
11. SEE SUNOCO PENNSYLVANIA PIPELINE PROJECT ESRI WEBMAP FOR ACCESS ROAD ALIGNMENT.
12. SUNOCO PIPELINE, L.P.'S HORIZONTAL DIRECTIONAL DRILL INADVERTENT RETURN CONTINGENCY PLAN WILL BE IMPLEMENTED AT ALL TIMES.
13. SUNOCO PIPELINE, L.P.'S EROSION AND SEDIMENTATION CONTROL PLAN WILL BE IMPLEMENTED AT ALL TIMES.

NOTES
1. ALL COORDINATES SHOWN ARE IN LATITUDE AND LONGITUDE. ALL MSL ELEVATIONS ARE NAD83
2. STATIONING IS BASED ON HORIZONTAL DISTANCES.
3. ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP ARE NOT RESPONSIBLE FOR LOCATION OF FOREIGN UTILITIES SHOWN IN PLOT PLAN OR PROFILE. THE INFORMATION SHOWN HEREON IS FURNISHED WITHOUT LIABILITY ON THE PART OF ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP, FOR ANY DAMAGES RESULTING FROM ERRORS OR OMISSIONS THEREIN.
4. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES. CONTACT ONE CALL AT 811 PRIOR TO DIGGING.
5. SUNOCO EMERGENCY HOTLINE NUMBER IS #1-800-786-7440.

REF. DRAWING

ES-4.11	TO	ES-4.11	EROSION & SEDIMENT PLAN	
SHEET 7	TO	SHEET 7	AERIAL SITE PLAN	
DWG NO		DWG NO	DESCRIPTION	

REVISIONS

NO.	DESCRIPTION	BY	DATE	CHK	DATE	APP	DATE
EP2	REVISED PER PADEP COMMENTS RECEIVED 09-06-16	MRS	10/07/16	RMB	10/07/16	AAW	10/07/16
EP1	REVISED PER PADEP COMMENTS	MRS	05/09/16	RMB	05/09/16	AAW	05/09/16
EP		JTW	03/15/16	RMB	03/15/16	AAW	03/15/16
B	ADDED GEOTECH INFO	MRS	09/17/15	RMB	09/17/15	AAW	09/17/15
A	ISSUED FOR BID	MRS	08/31/15	RMB	08/31/15	AAW	08/31/15

Sunoco Logistics Partners L.P.

TETRA TECH ROONEY
(303) 792-5911

SUNOCO PIPELINE, L.P.

16-INCH HORIZONTAL DIRECTIONAL DRILL
I-83
PENNSYLVANIA PIPELINE PROJECT

SCALE: 1"=150'

DWG. NO: PA-YO-0040.0002-RD-16

LEGEND:

Geotechnical Soil Boring (SB) Locations

TETRA TECH

GEOTECHNICAL BORING LOCATIONS
HDD S2-0270
YORK COUNTY, FAIRVIEW TOWNSHIP, PA
SUNOCO PENNSYLVANIA PIPELINE PROJECT

TETRA TECH
240 Continental Drive, Suite 200
Newark, Delaware 19713
302.738.7551
fax: 302.454.5988

TEST BORING LOG

Project Name:	SUNOCO PENNSYLVANIA PIPELINE PROJECT		Project No.: 103IP3406
Project Location:	411 GURTNER ROAD, NEW CUMBERLAND, PA		Page 1 of 1
HDD No.:	S2-0270	Dates(s) Drilled: 10-28-14	Inspector: E. WATT
Boring No.:	SB-01	Drilling Method: SPT - ASTM D1586	Driller: S. HOFFER
Drilling Contractor:	HAD DRILLING	Groundwater Depth (ft): NOT ENCOUNTERED	Total Depth (ft): 18.1

Sample No.	Sample Depth (ft) From	Sample Depth (ft) To	Strata Depth (ft) From	Strata Depth (ft) To	Recov. (in)	Strata (USCS)	Description of Materials	6" Increment Blows *				N
			0.0	0.8			TOPSOIL (10")					
1	3.0	5.0	0.8		7	FILL - SC	POTENTIAL HISTORICAL FILL: ORANGE BROWN FINE TO MEDIUM SAND	10	8	7	12	**15**
				6.5			WITH SOME SILTY CLAY AND F-C SANDSTONE GRAVEL.					
2	8.0	10.0	6.5		14	MH	DR WEATHERED TO A ORANGE TO YELLOWISH BROWN SILT	1	2	3	3	**5**
							AND FINE SAND, TRACE FINE ANGULAR GRAVEL (USCS: MH)					
3	13.0	15.0			19		DR WEATHERED TO A ORANGE TO YELLOWISH BROWN SILT	10	14	10	5	**24**
				17.0			AND FINE SAND, TRACE FINE ANGULAR GRAVEL.					
4	17.0	17.4	17.0		2		PARTIALLY WEATHERED LIGHT BROWN TO YELLOWISH BROWN	50/5"				**>50**
				18.1			SANDSTONE.					
							AUGER REFUSAL AT 17'. OFF-SET BORING AND CONTINUOUSLY					
							AUGERED TO REFUSAL AT 18.1'.					
							CAVED AND DRY AT 16'.					

Notes/Comments:
Pocket Pentrometer Testing

DR: DECOMPOSED ROCK

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
N: Number of blows to drive spoon from 6" to 18" interval.

TETRA TECH
240 Continental Drive, Suite 200
Newark, Delaware 19713
302.738.7551
fax: 302.454.5988

TEST BORING LOG

Project Name:	SUNOCO PENNSYLVANIA PIPELINE PROJECT		Project No.: 103IP3406
Project Location:	305 STONE ROW LANE, NEW CUMBERLAND, PA		Page 1 of 1
HDD No.:	S2-0270	Dates(s) Drilled: 10-28-14	Inspector: E. WATT
Boring No.:	SB-02	Drilling Method: SPT - ASTM D1586	Driller: S. HOFFER
Drilling Contractor:	HAD DRILLING	Groundwater Depth (ft): SEE BELOW	Total Depth (ft): 30.2

Sample No.	Sample Depth (ft) From	Sample Depth (ft) To	Strata Depth (ft) From	Strata Depth (ft) To	Recov. (in)	Strata (USCS)	Description of Materials	6" Increment Blows *				N
			0.0	0.4			TOPSOIL (5")					
			0.4	4.0		CL	MOTTLED GRAY AND BROWN SILTY CLAY, TRACE FINE SAND.					
1	3.0	5.0	0.4		14	SC, SC/GC WITH DEPTH	DR WEATHERED TO AN ORANGE BROWN TO LIGHT BROWN FINE	10	10	15	15	**25**
							SAND WITH SOME SILTY CLAY, TRACE FINE GRAVEL.					
2	8.0	10.0			10		DR WEATHERED TO AN ORANGE BROWN, GRAY AND LIGHT BROWN	2	17	50/5"		**>50**
							M-C SAND WITH A LITTLE SILTY CLAY.					
3	13.0	13.4			5		DR WEATHERED TO A REDDISH BROWN TO GRAY F-SAND WITH SOME	50/5"				**>50**
							F-C UNWEATHERED SANDSTONE GRAVEL, SOME SILTY CLAY.					
4	18.0	19.4			14		DR WEATHERED TO A VARI-COLORED FINE TO MEDIUM SAND, A	4	18	50/5"		**>50**
							LITTLE F-C SANDSTONE GRAVEL, SOME SILTY CLAY.					
5	23.0	23.8			5		DR WEATHERED TO A VARI-COLORED FINE TO MEDIUM SAND, SOME	4	50/4"			**>50**
							F-C SANDSTONE GRAVEL, WITH A LITTLE SILTY CLAY.					
6	28.0	28.8			3		DR WEATHERED TO A VARI-COLORED FINE TO MEDIUM SAND, SOME	4	50/4"			**>50**
				29.0			F-C SANDSTONE GRAVEL, WITH SOME SILTY CLAY.					
7	30.0	30.2	29.0	30.2	2		PARTIALLY WEATHERED MULTI-COLORED SANDSTONE.	50/3"				
							WET ON SPOON AT 29'.					
							WATER LEVEL THROUGH AUGERS AT 27'.					
							CAVED AT 28', WATER LEVEL ON CAVE AT 9'.					

Notes/Comments:
Pocket Pentrometer Testing

DR: DECOMPOSED ROCK

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
N: Number of blows to drive spoon from 6" to 18" interval.

TETRA TECH
240 Continental Drive, Suite 200
Newark, Delaware 19713
302.738.7551
fax: 302.454.5988

TEST BORING LOG

Project Name:	SUNOCO PENNSYLVANIA PIPELINE PROJECT		Project No.: 103IP3406
Project Location:	304 STONE ROW LANE, NEW CUMBERLAND, PA		Page 1 of 1
HDD No.:	S2-0270	Dates(s) Drilled: 10-28-14	Inspector: E. WATT
Boring No.:	SB-03	Drilling Method: SPT - ASTM D1586	Driller: S. HOFFER
Drilling Contractor:	HAD DRILLING	Groundwater Depth (ft): NOT ENCOUNTERED	Total Depth (ft): 17.9

Sample No.	Sample Depth (ft) From	Sample Depth (ft) To	Strata Depth (ft) From	Strata Depth (ft) To	Recov. (in)	Strata (USCS)	Description of Materials	6" Increment Blows *				N
			0.0	0.5			TOPSOIL (6")					
1	3.0	5.0	0.5	4.8	13	ML	MOTTLED GRAY AND BROWN SILT AND FIND SAND.	1	2	7	10	**9**
2	8.0	10.0	4.8		24	SM	MOTTLED MULTI-COLORED FINE TO MEDIUM SAND AND SILT, TRACE	2	13	16	25	**29**
							FINE STANDSTONE GRAVEL.					
3	13.0	13.8			7		YELLOOW BROWN TO ORANGE BROWN FINE TO COARSE SAND	9	50/4"			**>50**
				16.5			AND SILT, WITH A LITTLE FINE SANDSTONE GRAVEL.					
4	17.0	17.4	16.5	17.4	3		PARTIALLY WEATHERED SANDSTONE.	50/5"				**>50**
							AUGER REFUSAL AT 17.5'.					
							CAVED AND DRY AT 15'.					

Notes/Comments:

Pocket Pentrometer Testing
S1: 3.25 TSF
S2: > 4 TSF

DR: DECOMPOSED ROCK

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
N: Number of blows to drive spoon from 6" to 18" interval.

GEOTECHNICAL LABORATORY TESTING SUMMARY
SUNOCO PENNSYLVANIA PIPELINE PROJECT
HDD S2-0270

HDD No.	Test Boring No.	Sample No.	Depth of Sample (ft.) From	Depth of Sample (ft.) To	Water Content, % (ASTM D2216)	Percent Silts/Clays, % (ASTM D1140)	Atterburg Limits (ASTM D4318) Liquid Limit, %	Atterburg Limits (ASTM D4318) Plastic Limit, %	Atterburg Limits (ASTM D4318) Plasticity Index, %	USCS Classif. (ASTM D2487)
S2-0270	SB-01	1	3.0	5.0	10.1	26.6	-	-	-	-
		2	8.0	10.0	40.5	53.1	56	33	23	MH
		3	13.0	15.0	44.1	59.0	-	-	-	-
	SB-02	1	3.0	5.0	16.0	30.4	-	-	-	-
		2	8.0	10.0	10.2	24.9	-	-	-	-
		4	18.0	19.4	8.0	24.2	-	-	-	-
		5	23.0	23.8	5.7	20.8	-	-	-	-
		6	28.0	28.8	7.8	22.6	-	-	-	-
	SB-03	1	3.0	5.0	14.6	66.2	-	-	-	-
		2	8.0	10.0	14.1	44.4	NV	NP	NP	SM?
		3	13.0	13.8	11.8	46.0	-	-	-	-
		4	17.0	17.4	5.5	21.1	-	-	-	-

Notes:

1) Sample depths based on feet below grade at time of exploration.

REGIONAL GEOLOGY SUMMARY
SUNOCO PENNSYLVANIA PIPELINE PROJECT
HDD S2-0270

HDD No.	NAME	BORING NO.	REGIONAL GEOLOGY DESCRIPTION	GENERAL TOPOGRAPHIC SETTING	BEDROCK FORMATION	GENERAL ROCK TYPE	APPROX MAX FM THICKNESS (FT)	DEPTH TO ROCK (Ft bgs) based on nearby well drilling logs	NOTES / COMMENTS
S2-0270	Beshore	SB-01	**Gettysburg Fm -** reddish-brown to maroon silty mudstone and shale and soft, red-brown, medium- to fine-grained sandstone, with minor amounts of yellowish-brown shale and sandstone and thin beds of impure limestone.	Gently sloping to level upland	Gettysburg Fm	Silty mudstone-shale-sandstone w/ some impure limestone	16,000	31-45	
		SB-02							
		SB-03							

Note : Source of well log data - http://www.dcnr.state.pa.us/topogeo/groundwater/pagwis/records/index.htm. All other sources as referenced in comments section.

FIELD DESCRIPTION AND LOGGING SYSTEM FOR SOIL EXPLORATION

GRANULAR SOILS

(Sand, Gravel & Combinations)

Density	***N (blows)****
Very Loose	5 or less
Loose	6 to 10
Medium Dense	11 to 30
Dense	31to 50
Very Dense	51 or more

Relative Proportions

Description Term	*Percent*
Trace	1 - 10
Little	11 - 20
Some	21 - 35
And	36 - 50

Particle Size Identification

Boulders	8 in. diameter or more	
Cobbles	3 to 8 in. diameter	
Gravel	Coarse (C)	3 in. to ¾ in. sieve
	Fine (F)	¾ in. to No. 4 sieve
Sand	Coarse (C)	No. 4 to No. 10 sieve (4.75mm-2.00mm)
	Medium (M)	No. 10 to No. 40 sieve (2.00mm – 0.425mm)
	Fine (F)	No. 40 to No. 200 sieve (0.425 – 0.074mm)
Silt/Clay	Less Than a No. 200 sieve (<0.074mm)	

COHESIVE SOILS

(Silt, Clay & Combinations)

Consistency	***N (blows)****
Very Soft	3 or less
Soft	4 to 5
Medium Stiff	6 to 10
Stiff	11 to 15
Very Stiff	16 to 30
Hard	31 or more

Plasticity

Degree of Plasticity	*Plasticity Index*
None to Slight	0 - 4
Slight	5 - 7
Medium	8- 22
High to Very High	> 22

ROCK

(Rock Cores)

Rock Quality Designation (RQD), %	***Rock Quality Description***
0-25	Very Poor
25-50	Poor
50-75	Fair
75-90	Good
90-100	Excellent

N - Standard Penetration Resistance. Driving a 2.0" O.D., 1-3/8" I.D. sampler a distance of 18 inches into undisturbed soil with a 140 pound hammer free falling a distance of 30.0 inches. The number of hammer blows to drive the sampler through each 6 inch interval is recorded; the number of blows required to drive the sampler through the final 12 inch interval is termed the Standard Penetration Resistance (SPR) N-value. For example, blow counts of 6/8/9 (through three 6-inch intervals) results in an SPR N-value of 17 (8+9).

Groundwater observations were made at the times indicated. Groundwater elevations fluctuate throughout a given year, depending on actual field porosity and variations in seasonal and annual precipitation.

UNIFIED SOIL CLASSIFICATION SYSTEM [Casagrande (1948)]

Major Divisions			Group Symbols	Typical Descriptions	Laboratory Classifications		
Coarse Grained Soils (More than half of material is larger than No. 200 sieve)	Gravels More than half of coarse fraction is larger than No. 4 sieve	Clean gravel (Little or no fines)	GW	Well-graded gravels, gravel-sand mixtures, little or no fines	Determine Percentage of sand and gravel from grain size curve. Depending on Percentage of fines (fraction smaller than No. 200 sieve), coarse-grained soils are classified as follows: Less than 5 percent GW, GP, SW, SP; More than 12 percent GM, GC, SM, SC; 5 to 12 percent Borderline cases requiring dual symbols[1]	$C_u=\frac{D_{60}}{D_{10}}$ greater than 4: $C_c=\frac{(D_{30})2}{D_{10} \times D_{60}}$ between 1 and 3	
			GP	Poorly graded gravels, gravel-sand mixtures, little or no fines		Not meeting C_u or C_c requirements for GW	
		Gravel with fines (Appreciable amount of fines)	GM	Silty gravels, gravel-sand-silt mixtures		Atterberg limits below A Line or I_p less than 4	Limits plotting in hatched zone with I_p between 4 and 7 are borderline cases requiring use of dual symbols
			GC	Clayey gravels, gravel-sand-clay mixtures		Atterberg limits above A line with I_p greater than 7	
	Sands (More than half of coarse fraction is smaller than No. 4 Sieve)	Clean sands (Little or no fines)	SW	Well graded sands, gravely sands, little or no fines		$C_u=\frac{D_{60}}{D_{10}}$ greater than 6: $C_c=\frac{(D_{30})2}{D_{10} \times D_{60}}$ between 1 and 3	
			SP	Poorly graded sands, gravelly sands, little or no fines		Not meeting C_u or C_c requirements for SW	
		Sands with fines (Appreciable amount of fines)	SM	Silty sands, sand-silt mixtures		Atterberg limits below A Line or I_p less than 4	Limits Plotting in hatched zone with I_p between 4 and 7 are borderline cases requiring use of dual symbols
			SC	Clayey sands, sand-clay mixtures		Atterberg limits above A line with I_p greater than 7	

Major Divisions		Group Symbols	Typical Descriptions
Fine-grained soils (More than half of material is smaller than No. 200 sieve)	Silts and clays (Liquid limit less than 50)	ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands, or clayey silts with slight plasticity
		CL	Inorganic clays of low to medium plasticity, gravelly clays , sandy clays, silty clays, lean clays
		OL	Organic silts and organic silty clays of low plasticity
	Silts and Clays (Liquid limit greater than 50)	MH	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts
		CH	Inorganic clays of high plasticity, fat clays
		OH	Organic clays of medium to high plasticity, organic silts
	Highly organic soils	Pt	Peat and other highly organic soils

For soils plotting nearly on A line use dual symbols i.e ., I_p = 29.5, w_L=60 gives CH-MH. When w_L is near 50 use CL-CH or ML-MH. Take near as ± 2 percent.



(1) Borderline classifications, used for soils possessing characteristics of two groups, are designated by combinations of group symbols. For example: GW-GC. well-graded gravel-sand mixture with clay binder.